

STANDARD PROVISIONS

-Applicant shall notify abutting properties through delivery of door hangers or letters three (3) working days, not including Saturday, Sunday, or holidays, prior to commencing work.

-Field verify locations and elevations of all existing utilities.

For the following, minimum clearances shall be measured from the outside of the proposed utility to the outside of the existing utility being encroached.

- Maintain **six (6)** foot horizontal and **two (2)** foot vertical clearance from all sanitary sewer mains and laterals. No utility shall cross a sanitary sewer main at an angle of less than 25 degrees parallel.

- Maintain **three (3)** foot horizontal and **two (2)** foot vertical clearance from all storm sewer pipe.

- Maintain **three (3)** foot horizontal and vertical clearance from all traffic signals, street lighting, traffic signs, City electrical or fiber conduit, handholes, and related City facilities.

- Maintain a minimum of **six (6)** foot horizontal clearance from all water mains, water services, valve boxes, and hydrants. When crossing all water mains, hydrant leads, and water services maintain a minimum of **two (2)** foot vertical clearance both above and below. No utility shall cross a water main or water service at an angle less than 25 degrees from parallel.

-No road or lane closings are allowed without permission of the Director of Public Works and a traffic control plan.

-All work zone signing and barricading shall be in accordance with [PART VI of the MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES \(MUTCD\)](#) and City of Fitchburg standards.

-All crews must have both a work zone safety and flagger's handbooks

-For removal or replacement of traffic and parking signs contact the public works department: [Public Works](#), (608) 270.4263

-The work area shall be backfilled, plated or protected by traffic control devices during non-working hours.

-NO EQUIPMENT OR MATERIALS shall be stored in the roadway or street right-of-way.

-All replacement items shall conform to the latest edition of City of Fitchburg [Standard Specifications](#) for Public Works Construction.

-Contractor shall restore/replace all pavement markings removed, disturbed, or damaged using the same materials as present within 30 days of completion. Markings shall be installed by a WisDOT pre-qualified contractor and shall meet WisDOT standard specifications. In the event the applicant fails to restore/replace markings as required within 30 days, the City retains the right to place markings and bill the applicant on a time and material basis, including engineering overhead. Invoice shall be paid within 30 days.

-All open trenches & bore pits shall be filled with compacted granular material to 95% modified proctor, the standard specification of ASTM D-1557. Top 6" shall be topsoil in terrace areas.

-Pavement patches shall be replaced in kind, minimum 12" crushed stone and 12.5mm asphalt to be at least 1" thicker than existing asphalt. Cold mix in winter (temporary), shall be replaced with hot mix by June 1.

-Sidewalks shall be concrete 5" thick (7" for driveway) with over 4" crushed aggregate base course (D.O.T. Gradation #3).

-All disturbed topsoil areas shall be seeded and outfitted with erosion matting for final restoration within 1 week of completion of work. Erosion Mat shall meet section 3.2.09 of the City of Fitchburg Standard Specifications for Public Works Construction.

-Per Fitchburg Code s. 70-145, vehicles over 10,000 lbs. gross weight shall use curb blocking with 4"x4" stock when mounting or crossing curb & gutter, unless specifically permitted in writing by Department. Gravel, stone, and/or soil curb ramping is expressly prohibited.